

## NCS DATA LOAD PROCEDURE

### 1. VERIFY TIME CONSTRAINTS FOR DATA LOAD

**NOTE:**

Determine if the Load requires a continuous uplink session or can be done with ZOE's.

Verify if the selected communications path supports performing the load in a reasonable amount of time for the MDM checksum safing response to be disabled.

### 2. LOG MDM CHECKSUMS

sel Software Health  
record CSCI Version ID \_\_\_\_\_

### 3. SELECT LOAD IMAGE FILE TO UPLINK

DNAV Command Inventory: Data Load Preparation

Data Load Preparation

sel Select Load File  
Navigate to the load image file you want to uplink  
If load image file is a PPL  
√ Version - <is correct version>

**NOTE:**

The user must select the proper version of the load image file. There will be separate files for loads to DRAM and EEPROM. For PPLs there is only one file. For Adaption data there may be multiple files for a single update. For Software loads there may be only one large file.

√ Destination Device - (N1-1,N1-2, N1 Primary, N1 Secondary)

If load is to DRAM:

√ Memory Location - DRAM

If load is to EEPROM:

√ Memory Location - EEPROM

√ Start Address - (should correspond to the address specified in the VDD)

√ Word Count - (should correspond to the size specified in the VDD)

Optional:

√ Metering Rate - should be 1.00 for OIU cmd path, .67 for Early Comm  
input Priority - (None, High, Urgent, Critical)  
input Uplink after: (time to uplink data load after)  
input Uplink by: (time to perform uplink by)  
input Remarks: (Remarks to FMT Manager)

sel Submit to FMT

#### 4. COORDINATION WITH THE FMT MANAGER

DVIS Call ODIN on the FMT DVIS loop to coordinate Uplink request. ODIN will perform MDM configuration and uplink of data load.

#### 5. VIEWING LOAD STATUS

CDDT Node 1:C&DH:Primary(Secondary) MDM

NODE 1:C&DH:MDM:Primary(Secondary)

√ Frame Count - <Incrementing> (MDM is operational)

NOTE:

Checksum errors may occur during the load process.

Sel MDM BIT Status

√ BST A word # 24 - X

√ BST A word # 2 - X

DNAV Uplink Manager

Uplink FMT Manager

√FMT\_Load\_Status- 100% complete

Record Data Load Commands \_\_\_\_\_

#### 6. MAKING DATA LOAD PERMANENT

Repeat this procedure if also loading to EEPROM.